

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

SECSWSE

API NUMBER 1216159 15-015-19062000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Hinz

WELL NUMBER #3

330 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 13 TWP. 23 RGE. 3 (E) or (W)

COUNTY Butler

Date Well Completed 12/59

Plugging Commenced 4/26/01

Plugging Completed 4/27/01

LEASE OPERATOR Te-Pe Oil & Gas

ADDRESS P.O. Box 522, Canton, Kansas 67428

PHONE# (620) 628-4428 OPERATORS LICENSE NO. 5920

Character of Well Input

(~~Oil~~) Gas, D&A, SWD, (Input), Water Supply Well)

The plugging proposal was approved on 4/25/01 (date)

by Butch Hobrecht (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Mississippi Depth to Top 2464 Bottom 2492 T.D. 2492

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Oil and Water	130	0	8-5/8	130	0
		2464	0	5-1/2	2464	0

MAY 2 2001

CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Filled bottom of 5-1/2" casing with sand to 2400'. Dump 5 sacks cement on bottom with bailer.
Fill casing with fresh water to 250'. Bridge 5-1/2" casing at 250' and fill with cement to top.
Run 1-1/4" pipe down 8-5/8" X 5-1/2" annulus to 250' and circulate 8-5/8" X 5-1/2" annulus with cement to top. Cut off casing 3' below ground level and cap with cement.

Name of Plugging Contractor Cyclone Well Service, Inc. License No. 3038

Address P.O. Box 522, Canton, Kansas 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Te-Pe Oil & Gas


STATE OF Kansas COUNTY OF McPherson, ss.

Terry P. Bandy (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Terry P. Bandy

(Address) P.O. Box 522, Canton, KS 67428

SUBSCRIBED AND SWORN TO before me this 30th day of April, 2001



Cynthia G. Reimer
Notary Public

Commission Expires: May 15, 2002

GRS