

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

WELL PLUGGING RECORD

15135-27081-0000

Give All Information Completely  
 Make Required Affidavit

COUNTY MISS SEC. 19 TWP. 18 RGE. 21 SW  
 Location as in quarters or footage from lines:

NW 1/4; 330' from South line & 500' from West line

Lease Owner JON M. CARROLL

Lease Name Roth Well No. 1

Office Address 3323 19th Great Bend, KS 67530

Character of Well (Completed as Oil, Gas or Dry Hole): OIL

Date Well Completed Drilled in Aug 81 by Mack Oil - Completed

Application for plugging filed Dec 28, 1982

Plugging commenced 21 Dec 82

Plugging completed 21 Dec 82

Reason for abandonment of well or producing formation

Depleted Oil formation

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well STEVE DURANT

Producing formation MISS. Depth to top 4223' bottom 4240' T.D. 4346'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>MISS.</u>	<u>OIL</u>	<u>4223'</u>	<u>4240'</u>	<u>8 3/8</u>	<u>418'</u>	<u>NONE</u>
				<u>4 1/2</u>	<u>4346'</u>	<u>875'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged well with 75 sacks 50-50 per sack cement 4% gel 3% CC from 1400' to 1707'. Then plugged with 50 sacks 50-50 per sack 4% gel 3% CC from 1380' to 1400'. Then wiped plug then plugged with mud 16 sacks of gel then plugged from 6'15" to surface with 100 sacks of 50-50 per sack cement 4% gel 3% CC

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 30 1982  
 12-30-82  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this form)  
 Name of Plugging Contractor \_\_\_\_\_

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jon M. Carroll  
3323 19th  
Great Bend, KS 67530  
 (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 1982

Elaine Mauck  
 Notary Public.

My Commission expires:

