

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,501-00-0

LEASE NAME Hinz 'B'

WELL NUMBER 1-22

SW SE NW
2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 22 TWP. 32S RGE. 14 XX or (W)

COUNTY Barber

Date Well Completed 11-03-82

Plugging Commenced 12-06-89

Plugging Completed 12-28-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texas Energies, Inc.

ADDRESS P.O. Box 947 Pratt, KS 67124

PHONE# (316) 672-7514 OPERATORS LICENSE NO. 5087

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-14-89 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Marmaton Depth to Top 4590 Bottom 4596 T.D. 4740

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	67	None
				8 5/8	1010	None
				5 1/2	4739	3820

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set cast iron bridge plug at 4530'. Dumped 2 sxs cement on top, pulled 5 1/2" casing. Pumped down 8 5/8" casing as follows: 31 bbls, fresh water with 500# hulls, 191 sxs 65% Class A cement with 35% pozmix A 10% gel mixed at 12.3#/gal. Max. press. 500#, ISIP 450#. Ran slick line, found top of cement at 275'. Filled to surface with approx. 3.6 cubic yards of readymix cement.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Texas Energies, Inc. License No. 5087

Address P.O. Box 947 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texas Energies, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.

Mark P. Stevenson (Employee of Operator) or Conservation Officer of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mark P. Stevenson

(Address) P.O. Box 947 Pratt, KS 67124

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1990

1-10-90
CONSERVATION DIVISION
Wichita, Kansas



SWORN TO before me this 8th day of January, 1990

Julia Berry
Notary Public

My Commission Expires: Feb. 6, 1993