

15-007-01445-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barber County, Sec. 25 Twp. 32S Rge. 11 (E) (W)

Location as "NE/CNW&SW" or footage from lines C NE/4 SE/4

Lease Owner Crescent Oil and Gas Corporation

Lease Name J. C. Elsea 'A' Well No. 1

Office Address P. O. Box 412, Tulsa 1, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10/19/60 as a dry hole 19 60

Application for plugging filed October 18 19 60

Application for plugging approved October 18, Verbally 19 60

Plugging commenced October 19 19 60

Plugging completed October 19 19 60

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Dry-None Depth to top Bottom Total Depth of Well 4965 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	270'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped in heavy mud from total depth to 265'. Set plug in 13 3/8" surface at 265'.
Ran 30 sacks of cement on top of plug through drill pipe. Put mud and hulls on top of cement to 35'. Ran second plug and cemented to the surface.
Plugged and Abandoned

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1960
10-25-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones
Address 514 Orpheum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
E. E. Reinkemeyer (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Reinkemeyer
P. O. Box 485, Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of October, 1960

My Commission Expires April 6, 1963

My commission expires _____ Notary Public.



GABBERT-JONES DRILLING CO., INC.

WICHITA, KANSAS

DRILLER'S WELL LOG

J. C. ELSEA A #1
 C NE SW SECTION 25-32S-14W
 BARBER COUNTY, KANSAS

COMMENCED 9-28-60
 COMPLETED 10-19-60

OPERATOR - CRESCENT OIL AND GAS CORPORATION

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	100	Gypgum & Red Bed	Ran 275' of 13-3/8" Casing, Cemented @ 270' w/300 sacks cement.
100	270	Red Bed	
270	1530	Red Bed	
1530	1735	Shale & Shells	
1735	2000	Shale & Lime	
2000	2615	Lime	
2615	3740	Shale & Lime	
3740	3895	Shale & Sandy Lime	
3895	4093	Lime & Shale	
4093	4131	Sand	
4131	4744	Lime	
4744	4844	Lime & Shale	
4844	4859	Lime	
4859	4868	Cherty Lime	
4868	4886	Lime	
4886	4932	Shale	
4932	4965	Lime	
4965	TD		

RECEIVED
 STATE GEOLOGICAL COMMISSION
 NOV 17 1960
 11-17-60
 CONSERVATION DIVISION
 Wichita, Kansas

DRY & ABANDONED

E. E. Reinke

E. E. Reinke