


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 34 Twp. 32S Rge. 14 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner Mull Drilling Company, Inc.

Lease Name Hull Well No. 1

Office Address 1625 Wichita Plaza Building Wichita, Kansas 67210

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 1-11-66 19

Application for plugging approved 1-14-66 19

Plugging commenced 1-18-66 19

Plugging completed 6-17-66 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving

Producing formation Depth to top Bottom Total Depth of Well PB 4798 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	215	None
				5 1/2	None	607'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaned out cellar. Killed gas. Pump 15 sacks of cement to 4700'. Blowing gas. Killing gas. Dumped 100' of sand and 3 sacks of cement. Working pipe. Shot pipe at 3975'. Circulating. Globe Oil Well Cementing, Inc. spotted 100 bbl of oil. Working pipe. Circulating. Globe Oil Well Cementing, Inc. spotted another 100 bbl of oil. Working pipe. Circulating. Globe Cementing, Inc. spotted 80 bbl. of oil. Working pipe. Shot pipe at 3000' - 2500' - 2000' - 1500' and 1000'. Working pipe. Shot pipe at 900' - 800' - 700' and 610'. Pulling pipe. Plugging well. Build rock bridge at 220'. Dumped 25 sacks of cement. Filled hole and rock bridge. capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1966
6-27-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of June, 19 66

My commission expires May 27, 1969

Notary Public.

ROTARY DRILLERS LOG

COMPANY : J. A. Mull, Jr. ROTARY DRILLING COMMENCED: 9-17-57
 Wichita, Kansas

CONTRACTOR : Mull Drilling Co., Inc. ROTARY DRILLING COMPLETED: 10-2-57
 Wichita, Kansas

CASING RECORD : Set 8 5/8" @ 200' cemented with 150 sacks cement.
 Set 5 1/2" @ 4803' cemented with 150 sacks cement.
 LOCATION: Hull #1
 NE NE SE 34-32S-14W
 Barber County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Red Bed	975
Shale & Shells	2000
Shale with Lime	2120
Lime	2385
Lime & Shale	3221
Sandy Lime & Shale	3535
Lime & Shale	4088
Lime	4763
Mississippi	4803

RECEIVED
 STATE CORPORATION COMMISSION

MAR 22 1966
 3-22-66
 CREATION DIV.
 Wichita, Kansas


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

By Joseph B. Brungardt, Jr.
 Joseph B. Brungardt, Jr., Asst. Treas.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 17th day of October, 1957.



Mudge N. Miller
 Notary Public

Commission Expires: February 24, 1960