

15-007-00380-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 29 Twp. 32S Rge. ~~13~~ 14 (W)

Location as "NE/CNW/SW" or footage from lines C NW SE
Lease Owner Pickrell Drilling Company
Lease Name Clark Well No. 1
Office Address 705 Fourth National Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 13, 19 57
Application for plugging filed December 13, 19 57
Application for plugging approved December 13, 19 57
Plugging commenced December 13, 19 57
Plugging completed December 14, 19 57
Reason for abandonment of well or producing formation D & A



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4856 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 225', bridge hole and cement with 30 sacks cement.
The heavy mud to 35' below ground level, bridge hole and cement with 10 sacks cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
12-26-57
DEC 26 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company,
Address 705 Fourth National Bank Bldg.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebits (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
705 Fourth National Bank Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 57

My commission expires July 30, 1958 [Signature] Notary Public.

PLUGGING
FILE SEC 29 T. 32 R. 4 W
BOOK PAGE 70 LINE 8

15-007-00380-0000
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 11/29/57

LOCATION: CNW/4 SE/4 Sec. 29-32-14W

Rotary Drilling Completed 12/14/57

Clark No. 1

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: 6 jts. 240' 8 5/8" Armco Spiralweld Casing cemented with 175 sacks cement circulated.

No oil string, D & A

LOG

(Figures indicate bottom of formation measurements from top of rotary bushing.)

Sand & Red Rock	115'
Hard Gyp	140'
Red Rock & Blue Shale	240'
Red Bed & Shale	1285'
Shale & Shells	1875'
Shale & Lime	2130'
Lime	2364'
Lime & Shale	2490'
Lime	2600'
Lime & Shale	3593'
Lime & Sand	3689'
Lime & Shale	4135'
Lime & Shale, Sand	4220'
Lime	4428'
Lime & Shale	4485'
Lime	4621'
Lime & Shale	4664'
Lime	4760'
Mississippi Lime	4780'
Mississippi	4805'
Lime	4856' T.D.

Circ. for samples at	4042'
	4198'
	4760'
	4770'
	4780'
	4805'
	4815'

S.I.M. at 1500 - O.K.
2500 - "
3500 - "
4500 - "

Slope Test at 1500 0° off
2500 0° off
3500 0° off
4500 0° off

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1957
12-26-57
CONCESSION DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 29 T 32 R 14W
BOOK PAGE 70 LINE 8

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

On this 20 day of December, 1957, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

[Signature]
Notary Public