

15-007-20912-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
REV. 12-15-80

OCT 13 1982  
10-13-82  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barber SEC. 11 TWP. 32 S RGE. 14 W E/W  
Location as in quarters or footage from lines:  
100 ft. SW - C SE 1/4


Lease Owner Robinson Oil Company  
Lease Name Lake Well No. J-1  
Office Address 300 W. Douglas - Suite 737 - Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
Date Well Completed 4-8-80  
Application for plugging filed 9-27-82  
Plugging commenced 9-28-82  
Plugging completed 10-11-82 - 2:30 p.m.  
Reason for abandonment of well or producing formation Dry

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Buddy Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4,427

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10 3/4	270	None
				8 5/8	1110	380
				4 1/2	4393	3593

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back at 4,353  
Sand from 4,353 to 4,050  
4 sacks cement with Dump Bailer = 4,050 to 4020  
Ripped 4 1/2 " at 3,592. Pulled and layed down.  
Ripped 8 5/8 at 600 and 380  
Allied pumped in 4 sacks hulls - 50 sacks cement  
30 sacks jell - 1 sack hull - 150 sacks  
50-50-POZ 4% jell - 3% C. C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.  
Elmer R. Mergens (employee of ~~owner~~) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Elmer R. Mergens  
Medicine Lodge, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of Oct., 1982

Jessie Hamilton  
Notary Public.

My Commission expires: April 4, 1986