

15-007-01357-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 18 Twp. 32S Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines C SE NW

Lease Owner Aylward Drilling Company

Lease Name Stumph-Smith "A" Well No. 3

Office Address 909 First National Bank Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed November 14 1958

Application for plugging filed October 11 1965

Application for plugging approved October 12 1965


Plugging commenced October 12 1965

Plugging completed October 16 1965

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production September 19 65

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. Elving

Producing formation Mississippian Depth to top Bottom Total Depth of Well 4775 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	None
				4 1/2"	4775'	3393'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4750 feet to 4700 feet for each plug set.

Hole plugged with 30' of chat and 30' cement (3 sacks)
Built bridge at 215' with 10' rock and 25 sacks cement
Filled with mud to 40' of top
Built bridge at 40' with 10' rock and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1965

11-19-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

Address Medicine Lodge, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Duane Jessup

(employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Duane Jessup

909 1st Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22 day of October, 19 65

My commission expires May 14, 1968

JOSEPH A. HESS
Notary Public.

STUMPH-SMITH "A" NO. 3

Casing Record:
 8 5/8" - 215'
 4 1/2" - 4775'

Company: Aylward Drilling Company &
 Bachus Oil Company
 Contractor: Aylward Drilling Company
 Commenced: October 29, 1958
 Completed: November 14, 1958

Location: C SE NW 18-32-14W
 Barber County
 Kansas
 Elevation: 1870 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand & Gravel	0	50	Set 8 5/8" surface pipe @ 215' w/175 sacks cement.
Gyp & Red Bed	50	131	
Gyp & Red Rock	131	440	Geological Tops:
Red Rock & Gyp	440	1003	
Shale & Shells	1003	1030	Heebner Shale 3941
Shells & Shale	1030	1555	B/Oread 3978
Shale & Shells	1555	1675	Douglas Sand 4085
Shale & Lime	1675	1805	Lansing 4116
Lime w/Shale	1805	2060	B/Kansas City 4566
Mostly Lime	2060	2115	Mississippian 4624
Lime	2115	2240	T.D. 4774
Lime w/Shale	2240	2330	DST 4620-49 Open 1 hr. Gas surf. in 2 min., gauged 1,350 MCFG/5", 1,630M/10", 1,930 M/15" & 1 hr. Rec. 6" mud. IBHP 1630#/30", FBHP 1590#/30". FP. 335#-350#.
Lime	2330	2550	
Lime & Shale	2550	2590	
Lime w/some Shale	2590	2735	
Lime & Shale	2735	2995	
Shale & Lime	2995	3455	
Lime & Shale	3455	3945	
Sandy Lime & Shale	3945	3959	
Lime & Shale	3959	4092	
Lime & Sandy Shale	4092	4117	
Lime & Shale	4117	4212	
Lime	4212	4270	
Lime w/Shale	4270	4322	
Lime & Shale	4322	4330	
Lime	4330	4479	
Lime w/some Chert	4479	4522	
Lime	4522	4585	
Lime w/some Shale	4585	4635	
Lime w/Chert	4635	4686	
Lime w/some Chert	4686	4725	
Shale & Lime	4725	4763	
Lime & Shale	4763	4775 T.D.	5 1/2" Casing @ 4775' w/100 sax cement.

RECEIVED
 STATE CORPORATION COMMISSION

NOV 19 1965
 11-19-65
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 19th day of December 1958.

Duane Jessup
 DUANE JESSUP Notary Public

My commission expires December 11, 1961