

15-007-30254-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barber County, Sec. 33 Twp. 32S Rge. (E) 14 (W)
C NE

Location as "NE/CNW/SW" or footage from lines
Lease Owner Eason Oil Company
Lease Name Allen Well No. 1-33
Office Address Box 18755, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 19
Application for plugging filed 11-4-65 19
Application for plugging approved 11-8-65 19
Plugging commenced 11-5-65 19
Plugging completed 11-8-65 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 5065 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	250	None
				8 5/8	2350	1797.11

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Casing was shot at 2204, 2016, 1907, 1813 and 1787'. Hole was kept full of mud. Pulled 58 joints of 8 5/8" casing. Set bridge plug at 250 feet and put 50 sacks cement in hole. Filled 13 3/8" casing with mud to 40 feet. Set bridge plug at 40 feet and capped with 30 sacks cement.

12-16-65
DEC 16 1965

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gayle E. Toland & Co.
Address Box 94336, Oklahoma City, Oklahoma

STATE OF _____, COUNTY OF _____, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God?

(Signature) *[Handwritten Signature]*
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1965

My commission expires SEPTEMBER 11, 1966
Margie M. Corbin
Notary Public.



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

ALLEN #1
 C NE 1/4 SECTION 33-32S-14W
 BARBER COUNTY, KANSAS

COMMENCED: OCTOBER 17, 1965
 COMPLETED: NOVEMBER 2, 1965

OPERATOR: EASON OIL COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	70	SAND AND CLAY	
70	260	RED BED AND SHELLS	RAN 8 JOINTS 13-3/8" CASING, SET @ 250' w/250 BX. CEMENT.
260	385	RED BED	
385	973	RED BED AND SHALE	
973	1485	RED BED AND SHELLS	
1485	1730	SHALE AND LIME	
1730	1757	SHALE	
1757	2035	SHALE AND SHELLS	
2035	2165	SHALE AND LIME	
2165	2353	LIME	RAN 26 JOINTS 8-5/8" CASING, SET @ 2353' w/150 BX. CEMENT.
2353	2525	LIME AND SHALE	
2525	2635	LIME w/SAND AND CHERT	
2635	2776	LIME AND SHALE	
2776	2790	SHALE	
2790	3580	LIME AND SHALE	
3580	3825	LIME	
3825	4116	SHALE AND LIME	
4116	4280	SHALE AND SAND	
4280	4722	LIME	
4722	4824	LIME AND SHALE	
4824	4945	LIME	
4945	5065	SHALE AND LIME	
5065	TD		DRY AND ABANDONED.

RECEIVED
 STATE COMMISSION COMMISSIONER
 NOV 18 1965
 11-18-65
 COMMISSIONER DIVISION
 WICHITA, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE 1/4 SECTION 33-32S-14W, BARBER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 9TH DAY OF NOVEMBER, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.