15-135-19098-0000


Form CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ness County. Sec. 18 Twp. 18S Rge. 21W (E) (W)

Location as "NE/CNW¼SW¼" or footage from lines C SW SE

Lease Owner Beardmore Drilling Company

Lease Name Christensen Well No. 1

Office Address 827 Beacon Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 3, 1963 19

Application for plugging filed 12-3-63 19

Application for plugging approved 12-3-63 19

Plugging commenced 12-3-63 19

Plugging completed 12-3-63 19

Reason for abandonment of well or producing formation commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4289 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	349'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 540 w/ 20 sx. cement.
2nd plug @ 300 w/ 20 sx. cement
Top plug @ 40 w/ 10 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1963

12-11-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.

Address 510 Orpheum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Robert F. Walters (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters

510 Orpheum Building
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December 1963

Juanita M. Green
Juanita M. Green Notary Public.

My commission expires October 4, 1967

DRILLER'S LOG

15-135-19098-0000

COMPANY: BEARDMORE DRILLING COMPANY
827 BEACON BUILDING
WICHITA, KANSAS

WELL NAME: CHRISTENSEN NO. 1
C SW SE SEC. 18-18S-21W
NESS COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
510 ORPHEUM BUILDING
WICHITA 2, KANSAS

ROTARY DRILLING COMMENCED: NOVEMBER 20, 1963

ROTARY DRILLING COMPLETED: DECEMBER 3, 1963

ELEVATION: 2175 KB
2172 DF
2170 GL

CASING RECORD: 8 5/8" @ 349' w/ 175 sx. common cement w/ 2% cc.

LOG

0	5	Cellar
5	15	Soil
15	320	Shale
320	350	Sand
350	380	Sand
380	475	Shale and Sand
475	630	Shale and Shells
630	785	Sand and Shale
785	905	Red Bed and Shale
905	1145	Sand
1145	1190	Shale and Sand
1190	1445	Shale and Shells
1445	1482	Anhydrite
1482	1895	Shale and Shells
1895	2628	Shale and Lime
2628	2725	Lime and Shale
2725	3540	Shale and Lime
3540	3620	Lime and Chalk Streaks
3620	3680	Lime
3680	3738	Lime and Shale
3738	3870	Lime
3870	3920	Lime and Shale
3920	4025	Lime
4025	4080	Lime and Shale
4080	4146	Cherty Lime
4146	4210	Lime and Shale
4210	4279	Lime and Chert
4279	4289	Chert
	4289	Rotary Total Depth - D & A

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1963
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

Robert F. Walters

ROBERT F. WALTERS, Partner

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

BE IT REMEMBERED that, on this 9th day of December, 1963, before me, the undersigned, a Notary Public duly commissioned in and for the State and County aforesaid, came Robert F. Walters, known to me to be the same person who executed the foregoing instrument as Partner and in behalf of the Walters Drilling Co. and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires:
October 4, 1967

Juanita M. Green

Juanita M. Green, Notary Public