


15.135.20377.0600

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County, Sec. 17 Twp. 18S Rge. 21(W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Pickrell Drilling Company
Lease Name Gaede "C" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 20 1970
Application for plugging filed October 20 1970
Application for plugging approved October 20 1970
Plugging commenced October 20 1970
Plugging completed October 20 1970
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4265 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	275'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Bottom Plug @ 500' w/70 sacks cement, Middle Plug @ 240' w/20 sacks cement, Top Plug @ 40' w/10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
C. W. Sebitts
705 Fourth National Bank Building
Wichita, Kansas (Address)



Subscribed and Sworn to before me this 23rd day of October, 1970
Esther Lamone
Notary Public.

My Commission Expires January 19, 1973

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 10/11/70

Rotary Drilling Completed 10/20/70

LOCATION: Gaede "C" No. 1, C SE SE Section 17-18S-21W
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Ran 13 Jts. 8-5/8" surface casing set @ 275' KB. Cemented with
150 sacks cement. Completed 10:30 P.M. Circulated.

No oil string run. D & A, Plugged October 20, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

120	Post Rock		<u>C.F.S.</u>
275	Shale & Shells		4160
380	Sand		4180
650	Shale - Shells		4247
840	Red Beds - Shale		4265
1095	Sand		
1370	Red Beds - Shale		
1410	Shale & Red Beds		
1445	Anhydrite		<u>S.L.M.</u>
1760	Shale & Shells	Board	4164.83
2200	Shale & Lime	Strap	4163.68
2380	Lime - Shale		1.13 Difference
2685	Lime		
3318	Lime - Shale		
3665	Shale & Lime		<u>Slope Test</u>
4225	Lime		2000
4247	Cherty Lime		2500
4265	RTD		3000
			3500
			4000

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 23rd day of October, 19 70, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My Commission expires: January 19, 1973

[Signature]
Esther Lamone
Notary Public

