

AFFIDAVIT OF COMPLETION FORM

ACO-1


This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR TXO PRODUCTION CORP.
 ADDRESS 200 W. Douglas, Suite 300
Wichita, Kansas 67202
 **CONTACT PERSON Harold R. Trapp
 PHONE 265-9441
 PURCHASER Cities Service Co.
 ADDRESS 1600 Broadway, Ste. 900
Denver, CO 80202
 DRILLING H-30
 CONTRACTOR
 ADDRESS 251 N. Water
Wichita, KS 67202

API NO. 15-007-21.015-00-00
 COUNTY Barber
 FIELD ELSEA EXT.
 PROD. FORMATION Miss.
 LEASE Hull
 WELL NO. Hull "E" #1
 WELL LOCATION
1320 Ft. from South Line and
990 Ft. from West Line of
 the 35 SEC. 32S TWP. 14W RGE.

PLUGGING N/A
 CONTRACTOR
 ADDRESS N/A

TOTAL DEPTH 4783 PBD 4783
 SPUD DATE 10-9-80 DATE COMPLETED 11-12-81
 ELEV: GR 1964 DF _____ KB 1972



WELL PLAT
 KCC
 KGS
 MISC
 (Office Use)

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(AIR)~~ TOOLS (New) / (Used) casing.
 XXXXX XXXXX
 CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	24#	412'		400	
Production		2-7/8"	6.5#	4750'		150	

LINER RECORD			PERFORATION RECORD		
Top ft.	Bottom ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	N/A	N/A	N/A

TUBING RECORD		
Size	Setting depth	Packer set at
1 1/2"	4750	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/2500 gals 15% HCl @ 8 BPM	4750-4783'
Frac w/70-quality foam & 18,000# 20-40 sand @ 18 BPM	4750-4783'

RECEIVED
 KANSAS CORPORATION COMMISSION
 11-17-81
 NOV 17 1981

Date of first production <u>11-12-81</u>	Producing method (flowing, pumping, gas lift, etc.) <u>flowing</u>	Gravity <u>N/A</u>	CONSERVATION DIVISION Wichita, Kansas	
RATE OF PRODUCTION PER 24 HOURS	Oil <u>N/A</u> bbls.	Gas <u>215</u> MCF	Water <u>N/A</u> %	Gas-oil ratio <u>N/A</u> bbls.
Disposition of gas (vented, used on lease or sold) <u>Sold</u>		Perforations <u>N/A OH 4750-4783'</u>		

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

FIELD: Elsea Ext.

Name of lowest fresh water producing stratum Unknown Depth N/A

Estimated height of cement behind Surface Pipe Circulated to Surface

DV USED? _____

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
LOG TOPS				
Herington	2325	-353		
Florence	2556	-584		
Onaga Sh	3166	-1194		
Wabaunsee	3212	-1240		
Stotler	3366	-1394		
Howard	3497	-1525		
Topeka	3635	-1663		
Heebner	4056	-2084		
Douglas Group	4098	-2126		
Brn. Ls.	4244	-2272		
Lansing	4251	-2279		
Swope	4581	-2609		
Hertha	4622	-2650		
B/Kansas City	4657	-2685		
Pawnee	4692	-2720		
Miss.	4748	-2776		
RTD	4783			
PBD	4783			
Ran O.H. Logs				
DST #1, 4204-44' (Douglas Sd), w/results as follows:				
IFP/30": 278-823#				
ISIP/60": 1485#				
FFP/45": 850-1255#				
FSIP/90": 1476#				
Rec: 2400' SW				
DST #2, 4755-83' (Miss.), w/results as follows:				
IFP/30": 124-104#, GTS in 3", 725 MCFD				
ISIP/60": 655#				
FFP/45": 156-104#, stab. @ 773 MCFD				
FSIP/90": 624#				
Rec: 65' mud				

AFFIDAVIT

STATE OF KANSAS, COUNTY OF SEDGWICK SS, Mr.

Harold R. Trapp OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS District Geologist (FOR) ~~(OF)~~ TXO Production Corp.

OPERATOR OF THE Hull LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. "E" #1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 12th DAY OF November, 19 81, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Harold R Trapp

SUBSCRIBED AND SWORN BEFORE ME THIS 16th DAY OF November 19 81

STATEWIDE
NOTARY PUBLIC
Harvey County, Ks.

Pamela S. Goloff
NOTARY PUBLIC

My Comm. Expires 9/14/83
9/14/83