

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23300-00-00  
Spot: W2NWNESE Sec/Twnshp/Rge: 28-22S-13W  
2328 feet from S Section Line, 1202 feet from E Section Line  
Lease Name: LONG Well #: 1  
County: STAFFORD Total Vertical Depth: 3910 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3500		WITH 2 SX CMT
PROD	4.5	3909	1820	WITH 200 SX CMT
SURF	8.625	327		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2013 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, IN

Proposed Plugging Method: CIBP @ 3500' WITH 2 SX CMT. PLUG AT 790' WITH 10 SX GEL & 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.



Plugging Proposal Received By: NATHAN WILLIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/17/2013 10:00 AM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

SET CIBP @ 3500' WITH 2 SX CMT. 1ST PLUG AT 795' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3552	3558		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

KCC WICHITA  
JUL 29 2013  
RECEIVED

District: 01

Signed Nathan Willis  
8/02/13 (TECHNICIAN)

RECEIVED  
JUL 19 2013  
KCC DODGE CITY

