

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-193-20162-00-00  
Spot: SES Sec/Twnshp/Rge: 34-9S-33W  
660 feet from S Section Line, 3300 feet from E Section Line  
Lease Name: WIENS Well #: 2  
County: THOMAS Total Vertical Depth: 4730 feet

Operator License No.: 4967  
Op Name: BERENERGY CORPORATION  
Address: PO BOX 5850  
DENVER, CO 80217

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4183		
CIBP		4188		
CIBP		4370		
CIBP		4395		
CIBP		4400		
PROD	4.5	4718		225 SX
SURF	8.625	367		280 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2013 2:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DALE MUTTLBAUER Company: ALLIED CEMENT COMPANY Phone: (307) 689-9032

Proposed Plugging Method: Ordered 370 sx 60/40 pozmix 4% gel cement, 9 sx gel and 600 # hulls.  
Perforations: 4172' - 4178', 4164' - 4169', 4128' - 4134', 4060' - 4068'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/02/2013 2:00 PM KCC Agent: TOM CULLEY

Actual Plugging Report:

Perforated at 2700', 1670' and 300'.  
Ran tubing to 3980' and pumped 9 sx gel followed by 50 sx cement w/500 # hulls.  
Pulled tubing to 2700' and pumped 125 sx cement w/100 # hulls.  
Pulled tubing to 1668' and pumped 125 sx cement . Circulated cement to surface.  
Pulled tubing to 340' and pumped 60 sx cement . Filled 8 5/8" x 4 1/2" casing.  
Topped off 4 1/2" casing with 10 sx cement.

GPS: 39.22158 -100.99313

Perfs:

Top	Bot	Thru	Comments
4620	4622		
4304	4307		
4258	4260		
4172	4178		
4164	4169		
4128	4134		
4060	4068		

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 31 2013


CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED TICKET # 60338

Plugged through: TBG

District: 04

Signed

  
8/05/13 (TECHNICIAN)

JUL 19 2013

CM