

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21681-00-01
Spot: NWSWSW Sec/Twnshp/Rge: 28-30S-31W
1012 feet from S Section Line, 334 feet from W Section Line
Lease Name: PATTERSON B Well #: 1-28
County: HASKELL Total Vertical Depth: 5663 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5656	3120	WITH 175 SX CMT
SURF	8.625	1866		WITH 625 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/10/2013 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 50 SX CMT & 200# HULLS ON BOTTOM. PLUG AT 1900' WITH 20 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2013 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 50 SX CMT & 200# HULLS ON BOTTOM. TOC @ 4930'. 1ST PLUG AT 1905' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 593' WITH 50 SX CMT. 3RD PLUG AT 41' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5362	5370		
4996	5002		PAWNEE
4990	5002		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA

JUL 29 2013

RECEIVED

District: 01

Signed Eric MacLaren (TECHNICIAN)
8/03/13

RECEIVED

JUL 19 2013

KCC DODGE CITY