

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23819-00-00
Spot: S2NWSESW Sec/Twnshp/Rge: 14-30S-12W
848 feet from S Section Line, 1671 feet from W Section Line
Lease Name: KUMBERG Well #: 1-14
County: BARBER Total Vertical Depth: 4760 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		3000		
PROD	5.5	4517	2416	WITH 225 SX CMT
SURF	10.75	333		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2013 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2634

Proposed Plugging Method: SAND BACK TO 4250' & 5 SX CMT. PLUG AT 720' WITH 15 SX GEL & 50 SX CMT. PLUG AT 380' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2013 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4240' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 740' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4300	4310		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

JUL 29 2013

Plugged through: CSG

RECEIVED

District: 01

Signed Steve Pfeifer
8/27/13 (TECHNICIAN)

RECEIVED

JUL 19 2013

KCC DODGE CITY