

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22395-00-00
Spot: NWSWNWSW Sec/Twnshp/Rge: 27-26S-11W
1917 feet from S Section Line, 193 feet from W Section Line
Lease Name: OB Well #: 27-41
County: PRATT Total Vertical Depth: 4538 feet

Operator License No.: 32119
Op Name: NORTHERN NATURAL GAS CO.
Address: 1111 S 103RD ST P O BOX 3330
OMAHA, NE 68124

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	190		WITH 240 SX CMT
MSCC	5.5	2726		WITH 305 SX CMT
PROD	5.5	4527	0	WITH 410 SX CMT
SURF	9.625	1860		WITH 530 SX CMT

Well Type: MON UIC Docket No: _____ Date/Time to Plug: 05/13/2013 1:00 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: STAN DOBLER Company: TRES MANAGEMENT Phone: (405) 842-7888

Proposed
Plugging
Method:

PLUG BACK TD = 4470'. RUN TBG TO 600' & CIRCULATE CMT BACK TO SURFACE UP 5 1/2" CASING.
PRESSRE TEST ALL ANNULUS WITH CMT TO 500 PSIG.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/13/2013 4:20 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

**WELL WAS DRILLED & NEVER PERFORATED DUE TO HOLE BEING
DEVIATED.**RAN 2 3/8" TBG TO 623'. PUMPED 100 SX CMT CIRCULATING TO
SURFACE UP 5 1/2" CASING. PULLED TBG OUT OF HOLE & TOPPED OFF 5 1/2"
WITH 5 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 1500 PSIG WITH CMT.
VISUALLY CHECKED 13 3/8" X 8 5/8" ANNULUS ON 5/14/13 & IT WAS FULL OF CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 30 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey
8/06/13

(TECHNICIAN)

RECEIVED

JUL 26 2013

KCC DODGE CITY