

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00533-00-00
Spot: SESENW Sec/Twnshp/Rge: 13-15S-18W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: LEIKER Well #: 5
County: ELLIS Total Vertical Depth: 3564 feet

Operator License No.: 30762
Op Name: OIL COMPANY OF AMERICA, INC.
Address: 1200 MAIN STE 310
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3564		150 SX
SURF	8.625	1158		550 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2013 9:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: DARREL HERL Company: OIL CO. OF AMERICA Phone: (785) 639-6800

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 50 sx sand and 800 # hulls.
Shot pipe at 1950' and 1850'.
Set CIB plug at 3000'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2013 9:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Spotted 40 sx of sand on bottom and spotted 2 sx of cement on top.
Shot casing at 1950'. Couldn't pull; Shot at 1850' and couldn't pull.
Ran tubing to 2077' and pumped 100 sx cement w/300 # hulls.
Pulled tubing to 1000' and pumped 100 sx cement w/200 # hulls.
Cement circulated.
POOH. Topped off casing with 25 sx cement.
Topped off braden head with 25 sx cement.
Checked fill on 07/19/13. Back side full and casing down 15'.

GPS: 38.74865 -099.27437

Perfs:

Top	Bot	Thru	Comments
3564	3576		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING TICKET # 56643

Plugged through: TBG

JUL 31 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Ray A. Dinkel
8/02/13

(TECHNICIAN)

CM

JUL 22 2013