

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20121-00-00
Spot: W2E2NESE Sec/Twnshp/Rge: 10-28S-21W
2002 feet from S Section Line, 533 feet from E Section Line
Lease Name: AUSTIN A Well #: 1
County: FORD Total Vertical Depth: 5120 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5119	1900	WITH 150 SX CMT
SURF	8.625	548		WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/16/2013 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: CARL W DURR Company: WOOLSEY OPERATING Phone: (620) 886-5606

Proposed Plugging Method: PUMP 35 SX CMT WITH 200# HULLS ON BOTTOM. PLUG AT 1360' WITH 15 SX GEL & 50 SX CMT. PLUG AT 580' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2013 3:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 35 SX CMT WITH 200# HULLS ON BOTTOM. 1ST PLUG AT 1340' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 585' WITH 50 SX CMT. 3RD PLUG AT 35' WITH 40 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4990	5014		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

KCC WICHITA

JUL 29 2013

RECEIVED

District: 01

RECEIVED

JUL 19 2013

KCC DODGE CITY

Signed

Eric MacLaren
8/06/13

(TECHNICIAN)