

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20187-00-00
Spot: SE Sec/Twnshp/Rge: 8-34S-26W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: PAINTER A Well #: 1
County: MEADE Total Vertical Depth: 6085 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5870		WITH 2 SX CMT
COND	13.375	346		
PROD	4.5	6085	2594	
SURF	8.625	1478		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/23/2013 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 5860' WITH 2 SX CMT. PLUG AT 1500' WITH 20 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT. PUMP DOWN 13 3/8" X 8 5/8" ANNULUS WITH 100 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2013 3:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5870' WITH 2 SX CMT. 1ST PLUG AT 1519' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 372' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5922	6034		MORROW
5915	5918		CHESTER

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 30 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

JUL 26 2013

KCC DODGE CITY

Signed

Eric MacLaren
8/01/13

(TECHNICIAN)

AAE