

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21722-00-00
Spot: SWNESESW Sec/Twnshp/Rge: 26-20S-16W
987 feet from S Section Line, 2290 feet from W Section Line
Lease Name: CLUTTER Well #: 2
County: PAWNEE Total Vertical Depth: 3798 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1024		WITH 450 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/19/2013 9:00 PM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: TOM BLAKE Company: ROYAL DRILLING INC Phone: (785) 483-6446

Proposed Plugging Method: 1ST PLUG AT 3750' WITH 50 SX CMT. 2ND PLUG AT 1060' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 06/20/2013 12:15 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

1ST PLUG AT 3750' WITH 50 SX CMT. 2ND PLUG AT 1060' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OILWELL CEMENTING.

Plugged through: DP


KCC WICHITA

JUL 29 2013

RECEIVED

District: 01

Signed



(TECHNICIAN)

RECEIVED

JUL 19 2013

KCC DODGE CITY

AMZ