

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21887-00-00
Spot: S2NWNWSW Sec/Twnshp/Rge: 9-21S-22W
2000 feet from S Section Line, 330 feet from W Section Line
Lease Name: COX Well #: 3-9
County: HODGEMAN Total Vertical Depth: 4352 feet

Operator License No.: 32331
Op Name: DK OPERATING INC.
Address: 24583 NW 208 RD
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	211		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/18/2013 1:00 PM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 1490' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 07/18/2013 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1490' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

KCC WICHITA

JUL 29 2013

RECEIVED

District: 01

Signed

Michael Maier
8/01/13

(TECHNICIAN)

RECEIVED

JUL 19 2013

KCC DODGE CITY

AM