

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21935-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 6-33S-6E
1668 feet from S Section Line, 4862 feet from E Section Line
Lease Name: ANDES Well #: 7
County: COWLEY Total Vertical Depth: 3150 feet

Operator License No.: 30169
Op Name: DOUBLE "D" OIL COMPANY, INC.
Address: 2009 JEAN CT
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2650		
PKR	4.5	2410		
PROD	4.5	3150		200 SXS CMT
SURF	8.625	202		90 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2013 8:00 AM
Plug Co. License No.: 5495 Plug Co. Name: MCPHERSON, BILL AND/OR PENNY M. DBA MCPHERSON DRILLING
Proposal Rcvd. from: DONNY BUTLER Company: DOUBLE D OIL CO Phone: (620) 222-2500

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/07/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG & PACKER @ 2410' ATTEMPTING CEMENT SQUEEZE, CEMENTED TBG & PACKER IN HOLE W/150 SXS CEMENT. RIH ON WIRELINE & SHOT 2-3/8" TBG @ 180', LAYED DOWN TUBING. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 175'. RIH W/ 1" TBG @ 180'. MCPHERSON DRILLING PUMPED 35 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCUALTED. DANIELS READY MIX TICKET # 027688.

Perfs:

Top	Bot	Thru	Comments
3246	3250	CSG	
2320	2370	CSG	

KCC WICHITA

Remarks:

Plugged through: TBG

JUL 26 2013
RECEIVED

District: 02

Signed DUANE KRUEGER
8/07/13 (TECHNICIAN)