

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21420-00-00
Spot: SENWSW Sec/Twnshp/Rge: 4-21S-6W
1650 feet from S Section Line, 990 feet from W Section Line
Lease Name: FEE Well #: 6
County: RICE Total Vertical Depth: 3500 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3400		
PROD	4.5	3495		225 SX
SURF	8.625	223		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2013 10:00 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: FG HOLL Phone: (620) 564-3831

Proposed
Plugging
Method:

PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 07/15/2013 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP AT 3400' AND CAP WITH 2 SX'S CEMENT.
PERFORATE AT 1000', 600', AND 275'. RUN TUBIG TO 1000' AND PUMP 35 SX'S
CEMENT. PULL TUBIG TO 600' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 275'
AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3446	3450	CSG	Mississippian

Remarks: 60-40 POZ, 4% GEL. ALLIED TICKET 60469. XCEL WIRELINE 0095.

Plugged through: TBG

KCC WICHITA

JUL 26 2013

RECEIVED

District: 02

Signed

Virgil Clothier
8/07/13
(TECHNICIAN)