

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21541-00-00
Spot: N2NENWNE Sec/Twnshp/Rge: 1-35S-20W
10 feet from N Section Line, 1650 feet from E Section Line
Lease Name: PETTY Well #: 1-1
County: COMANCHE Total Vertical Depth: 6750 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	70		WITH 75 SX CMT
PROD	4.5	6745	3025	WITH 150 SX CMT
SURF	8.625	820		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2013 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL Phone: (620) 793-0915

Proposed Plugging Method: PUMP 35 SX CMT WITH 200# HULLS ON BOTTOM. PLUG AT 870' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: NONE
Date/Time Plugging Completed: 07/19/2013 10:30 AM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

PUMPED 35 SX CMT WITH 200# HULLS ON BOTTOM. 1ST PLUG AT 870' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
6244	6270		

Remarks: USED 60/40 POZMIX 4% GEL BY QULAITY WELL SERVICE.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 30 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

JUL 26 2013

KCC DODGE CITY

Signed

Nathan Willis
8/01/13

(TECHNICIAN)

MANZ