

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21910-00-01
Spot: SESWNW Sec/Twnshp/Rge: 15-29S-14W
2295 feet from N Section Line, 952 feet from W Section Line
Lease Name: CHINN Well #: 1
County: PRATT Total Vertical Depth: 4617 feet

Operator License No.: 31938
Op Name: INDIAN OIL CO., INC.
Address: PO BOX 209 2507 SE US 160 HWY
MEDICINE LODGE, KS 67104

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4290		WITH 2 SX CMT
PROD	4.5	4617	1962	WITH 200 SX CMT
SURF	8.625	337		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/16/2013 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4290' & 2SX CMT. PLUG AT 840' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2013 1:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4290' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 842' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 356' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4344	4350		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

JUL 29 2013

RECEIVED

District: 01

Signed Steve Pfeifer
8/07/13 (TECHNICIAN)

RECEIVED
JUL 19 2013
KCC DODGE CITY

AW