

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26571-00-00
Spot: SENESWSW Sec/Twnshp/Rge: 21-12S-16W
760 feet from S Section Line, 1100 feet from W Section Line
Lease Name: DONALD Well #: 1-21
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3596		180 SX
SURF	8.625	859		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2013 9:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: KEVIN STRUBE Company: SAMUEL GARY JR AND ASSOS. IN Phone: (620) 214-0454

Proposed Plugging Method: Ordered 225 sx 60/40 pozmix 4% gel cement and 400 # hulls.
PBTD-3551'
KC perfs-3263'
ARB-CIBP-3480'
LKC-CIBP at 3213'
GPS: 38.98951 -099.10926
781' FSL 4135' FEL SE NE SW SW

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2013 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Pioneer shot off casing at 2026'.
Alliance Well Service pulled casing to 1185'. Quality mixed and pumped 50 sx cement.
Pulled casing to 910' and pumped 30 sx cement.
Pulled casing to 680' and pumped 70 sx cement w/200 # hulls mixed in.
Pulled casing to 250' and pumped 70 sx cement w/200 # hulls mixed in to circulate cement to surface.
Pulled casing. Topped off with 5 sx cement. Hole standing full.

Remarks: QUALITY OILWELL CEMENTING TICKET # 7450

Plugged through: CSG


RECEIVED
KANSAS CORPORATION COMMISSION

AUG 23 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed


9/12/13

(TECHNICIAN)

CM

AUG 21 2013