

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21290-00-00
Spot: SWSENE Sec/Twnshp/Rge: 6-31S-5W
2310 feet from N Section Line, 990 feet from E Section Line
Lease Name: OLIVIER D Well #: 2
County: HARPER Total Vertical Depth: 3774 feet

Operator License No.: 34280
Op Name: BLUE SKY INVESTMENTS LLC
Address: PO BOX 477
HARPER, KS 67058

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3764	2340	175 SX
SURF	8.625	328		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2013 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (580) 541-7750

Proposed Plugging Method: SAND ABOVE PERFS & 4 SKS. REC PIPE, 35 SX 900', 35 SX 550', CIRC 375'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/23/2013 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SAND TO 3600' & 4 SKS CEMENT. REC'D 2340 OF 4 1/2" CASING. PULLED 4 1/2 TO 900', SPOTTED 35 SX CEMENT. PULLED 4 1/2 TO 550' SPOTTED 35 SX CEMENT. PULLED CASING 50 375' & CIRCULATED CEMENT TO SURFACE WITH 160 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3664	3674	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 05 2013
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60/40 4% GEL. QUALITY WELL SERVICE CEMENTING. COMPLIANCE TA

Plugged through: CSG

District: 02

Signed _____

[Handwritten Signature]
9/29/13 (TECHNICIAN)

[Handwritten mark]