

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26574-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 24-15S-16W
775 feet from N Section Line, 720 feet from W Section Line
Lease Name: ROSEMARY Well #: 1-24
County: ELLIS Total Vertical Depth: 3570 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	778		350 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/12/2013 12:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RICK Company: VAL ENERGY, INC. Phone: (620) 793-4859

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 08/12/2013 9:45 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3470 w/50 sx
2nd plug @1000 w/25 sx
3rd plug @825 w/40 sx
4th plug @600 w/80 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 23 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed CASE MORRIS
8/12/13 (TECHNICIAN)

AUG 14 2013