

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21942-00-01
Spot: NESENEW Sec/Twnshp/Rge: 34-23S-30W
880 feet from N Section Line, 2360 feet from W Section Line
Lease Name: PAMELA 2330 Well #: 1-34 RE
County: FINNEY Total Vertical Depth: 5420 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4370		WITH 2 SX CMT
CIBP		4590		WITH 2 SX CMT
CIBP		4800		WITH 2 SX CMT
CIBP		4920		WITH 2 SX CMT
PROD	5.5	5420		950 SX
SURF	8.625	346		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2013 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JAKE THOMAS Company: SANDRIDGE EXPLORATION Phone: (405) 323-1849

Proposed Plugging Method: CIBP @4360' cap w/2 sks cement [] 200 sk cement from 2050' to Surface [] Per KCC District office instructions

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 08/29/2013 12:05 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

CIBP SET @ 4370' WITH 2 SX CMT. 1ST PLUG AT 2057' WITH 100 SX CMT. 2ND PLUG AT 958' -0' WITH 100 SX CMT. TOP OFF WITH 10 SX CMT. PUMP 20 SX CMT DOWN BACKSIDE & PRESSURED TO 500 PSIG.

Perfs:

Top	Bot	Thru	Comments
5005	5013		
4981	4988		
4963	5013		
4856	4966		
4834	4864		
4723	4727		
4701	4705		
4680	4684		
4644	4648		
4613	4727		
4412	4443		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

SEP 04 2013

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

AUG 30 2013

KCC DODGE CITY

Signed

Daniel Sellers
9/12/13

(TECHNICIAN)

1927