

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22063-00-01
Spot: SESWNE Sec/Twnshp/Rge: 4-27S-12W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MISKIMEN Well #: 1-4
County: PRATT Total Vertical Depth: 4549 feet

Operator License No.: 9582
Op Name: STUDER OIL CO.
Address: PO BOX 925
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4549	1915	WITH 275 SX CMT
SURF	10.75	288		WITH 140 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/24/2013 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 100 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 100 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 07/24/2013 5:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 100 SX CMT. SHUT IN PRESSURE 1500#. TAG TOC @ 3760'. 1ST PLUG AT 600' WITH 20 SX GEL W/200# HULLS & 50 SX CMT. 2ND PLUG AT 300' WITH 100 SX CMT. 3RD PLUG AT 43' WITH 45 SX CMT. TOP OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4123	4159		
3851	3856		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 14 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL 3% CC BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED

AUG - 2 2013

KCC DODGE CITY

Signed

Eric MacLaren
9/18/13

(TECHNICIAN)