

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22108-00-00
Spot: E2E2SWNE Sec/Twnshp/Rge: 4-27S-12W
3300 feet from S Section Line, 1520 feet from E Section Line
Lease Name: MISKIMEN Well #: 2
County: PRATT Total Vertical Depth: 4423 feet

Operator License No.: 9582
Op Name: STUDER OIL CO.
Address: PO BOX 925
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4423	2005	WITH 275 SX CMT
SURF	10.75	337		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2013 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4075' WITH 5 SX CMT OR PUMP 35 SX CMT WITH 200# HULLS. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 100 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 07/25/2013 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED DOWN 5 1/2" CASING WITH 200# HULLS & 40 SX CMT. SHUT IN PRESSURE 1200#. TAG TOC @ 4050'. 1ST PLUG AT 600' WITH 15 SX GEL W/200# HULLS & 50 SX CMT. 2ND PLUG AT 360' WITH 100 SX CMT. 3RD PLUG AT 42' WITH 45 SX CMT. TOP OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4126	4176		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 14 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: **DENIED TA: LACK OF LEASE** USED 60/40 POZMIX 4% GEL 3% CC BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED
AUG -2 2013
KCC DODGE CITY

Signed Eric MacLaren
9/18/13 (TECHNICIAN)