

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23793-00-00
Spot: NWSESWW Sec/Twnshp/Rge: 25-33S-10W
342 feet from S Section Line, 4329 feet from E Section Line
Lease Name: CIRCLE INDUSTRIES 3310 Well #: 25-1
County: BARBER Total Vertical Depth: 6136 feet

Operator License No.: 34574
Op Name: SHELL GULF OF MEXICO INC.
Address: 150 N DAIRY-ASHFORD (77079) PO BO
HOUSTON, TX 77001

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		232		
CIBP		900		
CIBP		5260		
COND 18		60		WITH 28 SX CMT
PROD 7		5260	815	WITH 990 SX CMT
SURF 9.625		802		WITH 500 SX CMT

Well Type: SWD UIC Docket No: D31017.0 Date/Time to Plug: 07/29/2013 10:30 AM
Plug Co. License No.: 34896 Plug Co. Name: BAKER HUGHES OILFIELD OPERATIONS, INC.
Proposal Rcvd. from: MATT RANDOLF Company: SHELL GULF OF MEXICO Phone: (281) 506-1446

Proposed Plugging Method: SET CIBP @ 5170-5172'. TOP WITH 50 SX CMT. FILL WITH MUD TO 902'. SET CIBP @ 900-902'. CUT CASING AT 850'. FILL WITH 150 SX CMT. FILL WITH MUD TO 234'. SET CIBP @ 232-234'. FILL WITH CMT TO 5' BELOW GROUND LEVEL.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 07/30/2013 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 5260'. SPOTTED 10 BBL CMT ON TOP OF CIBP THROUGH TBG. LET CMT SET. TAG TOC @ 4939'. 1ST PLUG SET CIBP @ 900'. CUT 7" CASING AT 815'. LAID DOWN 7" CASING. RUN IN HOLE WITH 2 7/8" TBG. SPOT 14 BBL CMT ON TOP OF CIBP. LET CMT SET. TAG TOC @ 624'. 2ND PLUG SET CIBP @ 232'. CIRCULATE CMT TO SURFACE WITH 18.5 BBL CMT.

Perfs:

Remarks: USED CLASS H CMT BY BAKER HUGHES.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 14 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED
AUG - 2 2013
KCC DODGE CITY

Signed

Stephen J. Pfeifer
9/17/13
cc to MK 8/14/13
(TECHNICIAN)