

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-00292-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 27-25S-15W  
319 feet from S Section Line, 281 feet from W Section Line  
Lease Name: FRACK Well #: 1  
County: STAFFORD Total Vertical Depth: 4603 feet

Operator License No.: 3959  
Op Name: SIROKY OIL MANAGEMENT  
Address: PO BOX 464  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4200		WITH 2 SX CMT
PROD	5.5	4603	1860	WITH 800 GAL OF LATEX
SURF	8.625	281		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2013 9:00 AM  
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC  
Proposal Rcvd. from: SPENCER SIROKY Company: SIROKY OIL MANAGEMENT Phone: (620) 672-5625

Proposed Plugging Method: SET CIBP @ 4250' WITH 2 SX CMT. PLUG AT 950' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/09/2013 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4200' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 948' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. TOP WELL & CELLAR OFF WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4252	4266		

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP-04 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED

AUG 29 2013

KCC DODGE CITY

Form CP-2/3

Handwritten initials