

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07170-00-01
Spot: SWNENENE Sec/Twnshp/Rge: 34-20S-14W
4943 feet from S Section Line, 434 feet from E Section Line
Lease Name: PRITCHARD Well #: 1-2
County: BARTON Total Vertical Depth: 3545 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3480		
COND	12.5	240		w/250 sxs cmt
PROD	5.5	3541		150 SX
SURF	8.625	837		300 SX

Well Type: EOR UIC Docket No: E18207.3 Date/Time to Plug: 09/03/2013 12:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY Phone: (620) 793-9090

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 400 # hulls and 12 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/03/2013 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Casing has holes at 1340' - 1400'. Well has been squeezed. Tied to casing to circulate water from holes at 1340' - 1400' to surface.
Ran tubing to 3190' and pumped 12 sx gel followed by 75 sx cement.
Pulled tubing to 1400' and pumped 100 sx cement.
Pulled tubing to 700'. Circulated casing to surface with 70 sx cement.
Shut in casing and pumped 143 sx cement. Had circulation on surface pipe. Couldn't get cement to the surface. Shut in pressure 900 psi.
Tied to surface and pumped 112 sx cement down surface pipe. Shut in pressure 450 psi.
GPS: 38.27471 -098.84927

Perfs:

Top	Bot	Thru	Comments
3264	3450		

KCC WICHITA

Remarks: ALLIED CEMENTING TICKET # 61783

SEP 17 2013

Plugged through: CSG

RECEIVED

District: 04

Signed Bruce Rodie
9/17/13
(TECHNICIAN)
* CC to MIC 9/17/13

CM

SEP 06 2013