

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20600-00-00
Spot: NWSESWNE Sec/Twnshp/Rge: 17-27S-23W
3267 feet from S Section Line, 1964 feet from E Section Line
Lease Name: TORLINE 17A Well #: 1
County: FORD Total Vertical Depth: 5082 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|--------------------------|
| COND | 20 | 60 | | 8 YDS. |
| PC | | 1396 | | CEMENTED WITH 375 SX CMT |
| PROD | 5.5 | 5074 | 0 | WITH 175 SX CMT |
| SURF | 8.625 | 421 | | WITH 325 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2013 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: PUMP 35 SX CMT WITH 150# HULLS GEL SPACER TO 1400'. CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2013 1:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 35 SX CMT WITH 160# HULLS, 76 BBL MUD SPACER TO 1400' FOLLOWED BY 130 SX CMT TO SURFACE. PRESSURED TO 1900# & HELD AT 800#. PRESSURED THE BACKSIDE TO 200# WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4937 | 4947 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL WELL SERVICES.

Plugged through: CSG

District: 01

RECEIVED
SEP 12 2013
KCC DODGE CITY

Signed [Signature]
10/15/13 (TECHNICIAN)

KCC WICHITA

SEP 18 2013

RECEIVED

Form CP-2/3

[Handwritten initials]