

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21573-00-00
Spot: SWSSEW Sec/Twnshp/Rge: 29-14S-16W
330 feet from S Section Line, 1650 feet from W Section Line
Lease Name: DREILING K A Well #: 1
County: ELLIS Total Vertical Depth: 3485 feet

Operator License No.: 33905
Op Name: ROYAL DRILLING INC
Address: 719 WITT AVE PO BOX 342
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3483		125 SX
SURF	8.625	251		145 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2013 1:15 PM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: JOHN DRISCOLL Company: ROYAL DRILLING INC Phone: (785) 483-6446

Proposed	Ordered 400 sx 60/40 pozmix 4% gel cement; 500 # hulls.
Plugging	Perforations: LKC 3238' - 3374'. Open ARB.
Method:	Milled on well for 1 week. Tubing in hole at 2200'.
GPS: 38.79943 -099.12780	
329' FSL 3731' FEL	
SW SW SE SW	

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2013 3:30 PM KCC Agent: PAT STAAB

Actual Plugging Report: _____ Perfs: _____

<p>Nabors perforated at 1650' and 1047'. Holes already at 492'. Royal ran in hole with tubing to 2180'. Allied rigged to tubing and mixed and pumped 100 sx cement neat. Pulled tubing to 1100'. Allied rigged to tubing and mixed and pumped 200 sx cement w/500 # hulls to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 50 sx cement to pressure with 100 psi and 100 psi shut in pressure. Rigged to 8 5/8" casing and pumped 1 sx cement to pressure with 100 psi and 100 psi shut in pressure.</p>

KCC WICHITA
SEP 17 2013
RECEIVED

Remarks: ALLIED CEMENTING CO TICKET # 54861
Plugged through: TBG

District: 04

Signed [Signature] (TECHNICIAN) CM
10/16/13

SEP 11 2013