

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-055-21774-00-01
 Spot: NWSENESW Sec/Twnshp/Rge: 2-22S-30W
1968 feet from S Section Line, 1987 feet from W Section Line
 Lease Name: RENEE 2230 Well #: 1-2
 County: FINNEY Total Vertical Depth: 5595 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4190		WITH 2 SX CMT
CIBP		4240		
CIBP		4295		
CIBP		4650		
CIBP		4800		
CIBP		5110		
DVT		1250		WITH 130 SX CMT
DVT		5401		
PROD	5.5	5428	0	WITH 620 SX CMT
SURF	8.625	412		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2013 8:00 AM
 Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
 Proposal Rcvd. from: CHARLIE Company: SANDRIDGE EXPLORATION Phone: (405) 323-1849

Proposed Plugging Method: Set CIBP @ 4170' Cap with 2 sks cement. 200 sks cement inside 5 1/2" from 2050' to surface. CHECK BACKSIDE

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
 Date/Time Plugging Completed: 08/28/2013 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4190' WITH 2 SX CMT. FILL 5 1/2" CASING WITH CMT FROM 2057' TO 0' USING 220 SX CMT. PUMP 1 SX CMT DOWN ANNULUS TO 500#.

Perfs:

Top	Bot	Thru	Comments
5159	5182		
4807	4906		
4665	4781		
4306	4325		
4246	4260		
4212	4228		

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

SEP 12 2013

Plugged through: TBG

RECEIVED

RECEIVED

SEP - 4 2013


✓ 10/15/13

KCC DODGE CITY

[Handwritten signature]

District: 01

Signed



(TECHNICIAN)

Form CP-2/3

RECEIVED

SEP - 4 2013

KCC DODGE CITY

PG. 2 OF 2

POP: PENE 22:30 1-2

15-055-21774-0001

KCC WICHITA

SEP 12 2013

RECEIVED