

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-01038-00-00  
Spot: NWNENWSW Sec/Twnshp/Rge: 2-22S-19E  
2629 feet from S Section Line, 4314 feet from E Section Line  
Lease Name: UNIT 3 Well #: P-10  
County: ANDERSON Total Vertical Depth: 849 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	825		0 SX
SURF	7	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/09/2013 12:00 AM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: \_\_\_\_\_ Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out and top well off with cement. Tie onto tubing and squeeze cement until desired amount of pressure is achieved. Cut well off 3' below surface.

Plugging Proposal Received By: FORREST SUTHERLAND WitnessType: NONE  
Date/Time Plugging Completed: 04/09/2013 12:00 AM KCC Agent: FORREST SUTHERLAND

Actual Plugging Report:

RAN WORKSTRING TO BOTTOM, CEMENTED TO SURFACE. PULLED WORKSTRING OUT AND TOPPED WELL OFF WITH CEMENT. 4" HAD HOLE DOWNHOLE SO WE TIED ONTO 4" AND SQUEEZED CEMENT UNTIL GOOD CEMENT SLURRY CAME UP ON BACKSIDE OF 4". 100 SACKS USED.

Perfs:

Top	Bot	Thru	Comments
828	844		

RECEIVED  
SEP 16 2013  
KCC Chanute Dist. #3  
FS

Remarks:

Plugged through: TBG

KCC WICHITA  
SEP 20 2013  
RECEIVED

District: 03

Signed [Signature] (TECHNICIAN)