

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24811-00-00
Spot: SWSESE Sec/Twnshp/Rge: 19-19S-14W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: CALCARA Well #: 1
County: BARTON Total Vertical Depth: 3635 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3636	2404	175 SX
SURF	8.625	835		125 SX
T1	2.375	3548		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/18/2013 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2013 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with 5 sx cement.
Cut casing at 2404. Pulled casing to 1500' and pumped 140 sx cement w/200 # hulls.
Pulled casing to 950' and pumped 60 sx cement w/100 # hulls.
Pulled casing to 450' and circulated cement to surface with 150 sx cement.
Pulled casing. Hole stayed full.

GPS: 38.37712 -098.90702

Perfs:

Top	Bot	Thru	Comments
3547	3549		
3364	3366		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
8/15/13 (TECHNICIAN)

CM

JUL 30 2013