

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23793-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 12-15S-12W
1190 feet from S Section Line, 2175 feet from W Section Line
Lease Name: JS Well #: 1-12
County: RUSSELL Total Vertical Depth: 3470 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3469		150 SX
SURF	8.625	755		350 SX
T1	2.375	3438		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/22/2013 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/22/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with 5 sx cement.
Cut casing at 2425'.
Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls.
Pulled casing to 900' and pumped 60 sx cement w/100 # hulls.
Pulled casing to 450'. Circulated cement to surface with 200 sx cement and 100 # hulls.
Pulled casing. Hole stayed full.
GPS: 38.75846 -098.60681

Perfs:

Top	Bot	Thru	Comments
3087	3091		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

AUG 02 2013

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Bruce Rodie
8/15/13 (TECHNICIAN)

CM

JUL 30 2013