

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-30300-00-00  
Spot: SWNWNEW Sec/Twnshp/Rge: 31-31S-6E  
4942 feet from S Section Line, 3639 feet from E Section Line  
Lease Name: MCMINN Well #: 2  
County: COWLEY Total Vertical Depth: 1692 feet

Operator License No.: 33711

Op Name: B-C STEEL, LLC

Address: 209 N FRY ST  
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2314		0 SX
SURF	8.625	350		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/22/2013 8:00 AM  
Plug Co. License No.: 31074 Plug Co. Name: BRAKE, JOE DBA BRAKE INC.  
Proposal Rcvd. from: BRENT WHITMORE Company: GENDOR OIL CO Phone: (620) 218-5962

Proposed Plugging Method: Well was aqeezed with Cement & Drilled out when bit went through side at 1650', leaving the cement from 1650' to bbottom with a casing hole at 1650'. TD is currently at 1692' with cement below, I propose to cement 100' above casing leak @ 1650', then plug top 400 ft.. Note; log indicates cement to surface on back side of casing.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/25/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 1600, DUMP BAILED 4 SXS CEMENT ON TOP. DUG OUT CELLER. 4-25-2013, RIH W 1" TUBING ON BACKSIDE @ 300', PUMPED CEMENT TO SURFACE LAYED DOWN 1", RIH W/1" TUBING ON INSIDE @ 350'. CIRCUALTED TO SURFACE W/CEMENT. PUMPED 140 SXS 60/40 POZMIX TO SURFACE. P&A COMPLETE 5:00 PM 4-25-2013. DANIELS READY MIX CEMENT TICKET #28066.

Perfs:

Remarks: COMPLIANCE / 10 YEAR RULE

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

**AUG 13 2013**

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

Duane Krueger  
8/14/13  
(TECHNICIAN)