

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-19858-00-01

Spot: SWSWSW

Sec/Twnshp/Rge: 28-22S-13E

330 feet from S Section Line, 4950 feet from E Section Line

Lease Name: BLANCK UNIT

Well #: 11

County: GREENWOOD

Total Vertical Depth: 1796 feet

Operator License No.: 5193

Op Name: BARNARD, R.L. DBA BARNARD OIL O

Address: 907 S 3RD PO BOX 535
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		1746		
PROD	4.5	1781		30 SX
SURF	7	122		50 SX
T1	2.375	1746		

Well Type: EOR

UIC Docket No: E24991.1

Date/Time to Plug: 07/19/2013 9:00 AM

Plug Co. License No.: 7719

Plug Co. Name: CHEEVER WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD (DICK) BARNAR Company:

Phone: (620) 437-6343

Proposed Plugging Method: Plug above Bartlesville Sd., plug above Douglas Sd., plug from 50' to surface

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/19/2013 1:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1781' pumped 25 sxs cement, shot casing @ 811' & 250', ran tubing to 800' pumped 15 sxs cement pulled tubing to 250' pumped 70 sxs cement to surface, gel spacers between cement plugs.

Perfs:

RECEIVED

AUG 05 2013

KCC Chanute Dist. #3

mt

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 07 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Mike Duff
8/14/13 (TECHNICIAN)

cc to UK 8/07/13