

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19510-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 33-29S-8E
1051 feet from S Section Line, 3095 feet from E Section Line
Lease Name: FEE G Well #: 9
County: BUTLER Total Vertical Depth: 2087 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	2000		
PROD	7	2083		235 SX
SURF	10.75	53		40 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 05/08/2013 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: GEORGE RAYL Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/08/2013 3:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIN ON WIRELINE, SET CIBP @ 1850'. DUMP BAILED 2 SXS CEMENT ON TOP. DUG OUT CELLER, CEMENT @ SURFACE ON BACKSIDE OF 7". RIH W/TBG @ 500', GRESSEL OILFIELD ESTABLISHED CIRCULATION, MIXED & PUMPED 145 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 3:15 5-8-2013. CEMENT TICKET #40002

Perfs:

Top	Bot	Thru	Comments
1925	1988		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: DENIED TA

AUG 13 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

DUANE KRUEGER
8/14/13
(TECHNICIAN)

✓