

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24887-00-00  
Spot: NESWNWNW Sec/Twnshp/Rge: 27-20S-11W  
750 feet from N Section Line, 600 feet from W Section Line  
Lease Name: SESSLER Well #: A 1  
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3200		
PROD	5.5	3448	1585	250 SX
SURF	8.625	253		215 SX
T1	2.875	3282		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/26/2013 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (620) 793-2168

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/26/2013 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations. Topped off with 5 sx cement.  
Cut casing at 1585'. Pulled casing to 1300' and pumped 125 sx cement w/200 # hulls.  
Pulled casing to 900' and pumped 50 sx cement w/100 # hulls.  
Pulled casing to 600'. Circulated cement to surface with 150 sx cement and 150 # hulls.  
Pulled casing. Hole stayed full.  
GPS: 38.28811 -098.53312

Perfs:

Top	Bot	Thru	Comments
3396	3405		
3380			
3346	3364		
3310			
3260	3266		
3232	3240		
3160	3166		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie (TECHNICIAN) 8/14/13 CM

**JUL 31 2013**

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

**AUG 09 2013**

CONSERVATION DIVISION  
WICHITA, KS