

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-20807-00-00  
Spot: N2SW Sec/Twnshp/Rge: 36-26S-8W  
1980 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: MCCULLOUGH Well #: 5  
County: RENO Total Vertical Depth: 3711 feet

Operator License No.: 6139  
Op Name: BOYER, JAY C. ESTATE (DECEASED) D  
Address: PO BOX 511  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3710		125 SX
SURF	8.625	205		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/31/2013 4:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: NONE  
Date/Time Plugging Completed: 07/31/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report: SANDED BACK TO 3460' - CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2612' PULLED CASING TO 1300' SPOTTED 35 SX CEMENT. PULLED CASING TO 700' SPOTTED 35 SX CEMENT. PULLED CASING TO 255' CIRCULATED TO SURFACE WITH 200 SX CEMENT.

Perfs: \_\_\_\_\_  
RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 13 2013  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, 60/40 4% POS MIX, TICKET #41350  
Plugged through: CSG

District: 02 Signed B. J. Hope (TECHNICIAN)  
8/14/13