

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19172-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 17-25S-5E  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: L W ROBISON NORTH Well #: 29  
County: BUTLER Total Vertical Depth: 2554 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: 333 N PORTLAND AVE  
OKLAHOMA CITY, OK 73107

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	15.5	219		
L1	5.5	2554		
PROD	7	2439		
SURF	10.75	1705		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/23/2013 8:00 AM  
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL  
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY CO Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/26/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK W/(1500#) SAND @ 2475' DUMP BAILED 5 SXS CEMENT ON TOP OF SAND. TAGGED PLUG @ 2435'. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 270'-271', RIH W/TUBING @ 275', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 216 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCULATED. SDON. TAGED CEMENT @ 494' W/TUBING @ 304', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 88 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2547	2554		

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: CEMENT TICKET #38626 & 38625 -- TA LENGTH OF TIME

**AUG 13 2013**

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

DUANE KRUEGER  
8/14/13 (TECHNICIAN)

TJK