

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21924-00-00
Spot: SENESESW Sec/Twnshp/Rge: 33-27S-6E
2306 feet from S Section Line, 2944 feet from E Section Line
Lease Name: SIMMONS Well #: 1 X
County: BUTLER Total Vertical Depth: 3096 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 333 N PORTLAND AVE
OKLAHOMA CITY, OK 73107

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3094		80 SX
SURF	8.625	210		80 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2013 8:00 AM
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY Phone: (316) 321-0550

Proposed
Plugging
Method:

PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 05/16/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED WELL @ 3034 (1,000#), DUMP BAILED 5 SXS CEMENT ON TOP. TAGGED @ 2994. RIH ON WIRELINE, SHOT SQUEEZE HOLES 270'-277' (4 HOLES). RIH W/TUBING @ 275', CONSOLIDATED MIXED & PUMPED 123 SXS 60/40 POZMIX 2% CC TO SURFACE. CEMENT CIRCULATED ON BOTH STRINGS OF CASING. TAGGED CEMENT @ 120', CONSOLIDATED MIXED & PUMPED 30 SXS 60/40 POZMIX 2% CC TO SURFACE. P&A COMPLETE @ 5:00 PM 5-16-2013.

Perfs:

Top	Bot	Thru	Comments
3094	3096	OH	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: CEMENT TICKET #41647. DENIED TA

Plugged through: TBG

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

DUANE KRUEGER
8/14/13 (TECHNICIAN)

JK