

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21920-00-00
Spot: S2NWNESW Sec/Twnshp/Rge: 35-19S-12W
2300 feet from S Section Line, 1650 feet from W Section Line
Lease Name: HAMMER B Well #: 4
County: BARTON Total Vertical Depth: 3405 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3340		
PROD	5.5	3404		150 SX
SURF	8.625	315		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/23/2013 9:00 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER Phone: (620) 793-2645

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 12 sx gel.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1250', 600' and 290'.
Ran tubing to 3150' and pumped 12 sx gel followed by 60 sx cement w/100 # hulls.
Pulled tubing to 1300' and pumped 70 sx cement w/100 # hulls.
Pulled tubing to 650'. Circulated cement to surface with 125 sx cement and 300 # hulls.
Circulated on casing and surface pipe.
Pulled tubing and topped off with 5 sx cement.

GPS: 38.35391 -098.62132

Perfs:

Top	Bot	Thru	Comments
3116	3354		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: COPELAND ACID AND CEMENTING
Plugged through: ESGT06

AUG 02 2013
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Bruce Rodie
8/14/13 (TECHNICIAN) CM

JUL 30 2013