

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04876-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 9-20S-12W  
1650 feet from S Section Line, 990 feet from E Section Line  
Lease Name: HULME C Well #: 5  
County: BARTON Total Vertical Depth: 3446 feet

Operator License No.: 34434  
Op Name: EDISON OPERATING COMPANY LLC  
Address: 8100 E. 22ND ST. N., BLDG 1900  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3441		100 SX
SURF	8.625	201		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/26/2013 10:00 AM  
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.  
Proposal Rcvd. from: ROCH MILLER Company: EDISON OPERATING Phone: (620) 786-5161

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 10 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/26/2013 4:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 670' and 160'.  
Ran tubing to 3385' and pumped 10 sx gel followed by 40 sx cement w/100 # hulls.  
Pulled tubing to 1300' and pumped 50 sx cement w/100 # hulls.  
Pulled tubing to 680'. Circulated cement to surface with 160 sx cement and 150 # hulls on casing and surface pipe.  
Pulled tubing. Topped off with 5 sx cement.  
GPS: 38.32372 -098.64904

Perfs:

Top	Bot	Thru	Comments
3442	3446		

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: ALLIED CEMENTING

Plugged through: ESG 106

AUG 02 2013

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Bruce Rodie  
8/14/13 (TECHNICIAN)

CM

JUL 30 2013